




Technical Bulletin

TTJD-5

TekTips to Assist the Installer with Trouble-Free Installations

The release levers on this cover assembly are pre-set by Heartland Clutch to OEM specifications assuming a standard mechanical linkage release system and a new flywheel. If the release linkage system is hydraulic the installer must make the proper adjustments. It is critical to note that the flywheel on your installation should be carefully inspected to ensure that the proper depth of 2.844" is maintained without machining a flywheel too many times. **If machined too many times, the dowel pins will extend too far above the mounting surface of the flywheel and the cover will be crushed when bolted down.** The relief at the flywheel OD at the mounting surface must also maintain a depth or the cover will not seat properly. Catastrophic failure could result.



For additional application information please contact the Sales Department at **800-383-9204** or **sales@naclutch.com** For clarifications, or general technical assistance related or unrelated to this bulletin, please contact the Sales or Service Department at 1-800-383-9204. NACD-Heartland Clutch is always ready to assist you.